BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

SCHEDULE - B

Name of the Work : Repair of Anganvadi Building at Varadarajanagara, Vinayakanagara, Ramachandrapura, Singapura, Kuvempunagara and MS Palya in Ward No. 11, (Kuvempunagara), Vidyaranyapura Sub Division.

22

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates KRIDL		
				In Figures	Amount	In Words
1	38.52	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	193.98	7472.11	Rupees One Hundred Ninety Three and Ninety Eight Paise Only
2	71.95	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	235.32	16931.27	Rupees Two Hundred Thirty Five and Thirty Two Paise Only
3	110.46	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	25.44	2810.10	Rupees Twenty Five and Forty Four Paise Only
4	147.44	Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	199.28	29381.84	Rupees One Hundred Ninety Nine and Twenty Eight Paise Only
5	18.41	Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	4976.70	91621.05	Rupees Four Thousand Nine Hundred Seventy Six and Seventy Paise Only
6	15.34	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregtes @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	5874.52	90115.14	Rupees Five Thousand Eight Hundred Seventy Four and Fifty Two Paise Only

	Approved Qty.	Description	Unit	Schedule-B Rates		
				KRIDL		
				In Figures	Amount	In Words
7	5.04	Supply and fixing pressed steel door frames size 125x65 mm manufacture from 1.25mm thick carbon steel or imported steel strips with mitred joints of 900 for door openings and sutters made out of seasoned honne wood, styles of 30mm, thick with lock rail of 160mm, width, top and side rails of 100mm, width width and bottom rails of 250 mm width and panel filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be not proof, vermin proof, heat resistant guaranteed against shrinkage, warpage and such other defects for a period of 3 years, this shall be as per approved drawings, specification and direction including cost of conveyance, manufacturing, painting wit enamel paint 2 coats over primer coat, cost of labour for all items of work, machinery, equipment and all other incidental charges with all lead, lift, loading and unloading etc, complete the hollow portion of the frame to be filled with cement concrete1:2:4 etc complete as per specifications and	Sqm	3710.00	18698.40	Rupees Three Thousand Seven Hundred Ten Only
8	19.90	Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	4976.70	99036.33	Rupees Four Thousand Nine Hundred Seventy Six and Seventy Paise Only
9	39.14	Flooring with 25mm to 40mm thick polished **tandur blue stone slabs** using mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	1129.96	44226.63	Rupees One Thousand One Hundred Twenty Nine and Ninety Six Paise Only
10	123.48	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foregin matter including preparing the surface even and sand paper smooth, cost of materials, labours, etc complete as per specifications and directions of engineer in charge of the work.	Sqm	64.66	7984.22	Rupees Sixty Four and Sixty Six Paise Only
11	246.00	Providing and finishing external walls in tow coats with water proof cement paint of approve brand and shade to give an even shade after thourghly brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, etc complete as per specifications and directions of engineer in charge of the work.	Cum	83.74	20600.04	Rupees Eighty Three and Seventy Four Paise Only
12	50.00	Providing and fixing to wall, ceiling and floor, low density poluethylene pipes kgs/sq.cm working pressure **32mm** outside diameter, compression type fittings, wall clips, making good the wall ceiling and floor cost of materials, labour charges HOM of equipments and testing exeluding cost of fittings,etc complete as per specifications and directions of engineer in charge of the work.	Rmtr	193.98	9699.00	Rupees One Hundred Ninety Three and Ninety Eight Paise Only
13	5	Providing and fixing in position brass bib cock of approved quality 25 mm nominal bore including cost of all materials, labour and HOM of equipments with all leads etc complete as per specifications and directions of engineer in charge of the work.	Each	284.08	1420.40	Rupees Two Hundred Eighty Four and Eight Paise Only

	Approved Qty.	Description	Unit	Schedule-B Rates		
				KRIDL		
				In Figures	Amount	In Words
14	500	Supppying water storage tanks made of virgin polymer (LLDPE) with two layers outer black of blue and inner white layer of approved quality and make, conforming to ISI / ISO / SSI etc complete as per specifications and directions of engineer in charge of the work.	L	6.36	3180.00	Rupees Six and Thirty Six Paise Only
15	5	Supply patty type fluorescent tube light fitting of 4' - 36/40 watts fluorescent tube fitting, made out of M.S. Sheet and stove enameled with low loss open construction copper wound ferromagnetic ballast, starter, locking, locking type brass contact holder mounted on double fold type sheet base fully wired for used on 230 Volts A C Supply including fluouresecent tube etc complete as per specifications and directions of engineer in charge of the work.	Each	669.00	3345.00	Rupees Six Hundred Sixty Nine Only
16	5	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double ball bearing system Regulator Model (Khaitan, Crompton Geaves, Orient, Polar, Bajaj, Usha, Havells, Almonard etc complete as per specifications and directions of engineer in charge of the work.	Each	2376.00	11880.00	Rupees Two Thousand Three Hundred Seventy Six Only
		Total			458464.21	

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

24/x/16

29/10